Date: November 2, 2026

Addendum # 1

Title: Neqotkuk First Nation Lift Station Renewal Project

To All Bidders of F-24-NQ-07:

Please note: the following addendum applies to **F-24-NQ-07**and shall be taken into consideration when preparing bid documents.

General:

1. This addendum is issued prior to the closing to provide revisions as noted herein.
2. All such revisions will become part of the Work and the effects shall be included in the bid submission.

SECTION 00 21 16 – INFORMATION TO PROPONENTS

Page 1, clause 1.2 Tender Closing/Opening: revise to read: “Tender period will close on November 24th, 2026, at 2:00 pm local time”.

Page 9, clause 1.18 Owner Supplied Equipment

Add Clause 1.18.2: Owner supplied equipment availability is as follows:

- Gorman-Rupp (pump packages) – End of November 2026.
- Pre-fabricated building enclosures – End of November 2026 and will be stored at 1691 Route 133, Grand-Barachois, New Brunswick, E4P 8E4, Canada until requested by Contractor to be onsite.
- Control Panels – End of Dec 2026

SECTION 00 41 43 – TENDER FORM

Page 1, clause 1.3 COMPLETION TIME, delete in its entirety and replace with the following:

1.3 COMPLETION TIME

.1 The Tenderer shall provide its proposed date for Ready-for-Takeover of the Work:

Proposed Ready-for-Takeover Date: _____, but in no case later than June 30, 2027.

.2 The date proposed by the Tenderer shall become the contractual Ready-for-Takeover date upon execution of the Contract.

.3 The Tenderer shall account for all anticipated construction conditions, procurement, coordination of Owner-supplied equipment, installation, testing, start-up and commissioning necessary to achieve the proposed Ready-for-Takeover date.

.4 The Contractor shall be responsible for the construction means, methods, sequencing and scheduling necessary to achieve its proposed Ready-for-Takeover date.

SECTION 33 32 13 – PACKAGED WASTEWATER PUMPING STATIONS

Page 2, Clause 1.4.1 Delete in its entirety and replace it with the following:

The Owner will supply the pumping systems for three (3) suction-lift pumping stations. The Owner-supplied equipment for each station includes two (2) horizontal self-priming suction-lift pumping units, V-belt drives, motors, internal pipes, valves and fittings, air-release valves, gauge kits, flow meter, discharge connections, the complete prefabricated pump station enclosure/building and control panel(s) (6NQ_LS1_RTU01, 6NQ_LS2_RTU01 and 6NQ_LS3_RTU01), VFD(s) and ultrasonic level sensors. This equipment is Owner-supplied under separate procurement and shall be installed by the Contractor under this Section. Approved shop drawings identifying the Owner-supplied equipment are available to bidders upon request from AFNWA Procurement in accordance with Section 00 21 13.

A signed copy of each Addendum must also be included with the bid submission. Failure to include this Addendum may be cause for rejection. If you have any questions, please contact our office by email at procurement@afnwa.ca.

ALL OTHER SPECIFICATIONS, TERMS AND CONDITIONS REMAIN UNCHANGED.

Acknowledgement by Bidder:

Company Name: _____

Print Name: _____

Signed: _____

Date: _____

End of Addendum #1