Date: November 19, 2026

Addendum # 3

Title: Neqotkuk First Nation Lift Station Renewal Project

To All Bidders of F-24-NQ-07:

Please note: the following addendum applies to **F-24-NQ-07**and shall be taken into consideration when preparing bid documents.

General:

1. This addendum is issued prior to the closing to provide revisions as noted herein.
2. All such revisions will become part of the Work and the effects shall be included in the bid submission.

TO THE DRAWINGS:

1. Drawing C02– Sewage Lift Station #1 Existing Conditions and Proposed Layout: Revise note, “EXISTING I.D. 2100 DIA. WET WELL TO BE DEMOLISHED...” to read, “EXISTING I.D. 1800 DIA. WET WELL TO BE DEMOLISHED...”

2. Drawing C03 – Sewage Lift Station #1 Wet-Well Plan & Section: Revise all references identifying the existing wet well as 2100 mm diameter to 1800 mm diameter. The proposed wet-well dimensions are not changed by this correction.

3. Drawing C03 – Sewage Lift Station #1 Wet-Well Plan & Section: Revise note, “750 DIA. ADJUSTABLE FRAME AND COVER.” to read, “600 DIA. STANDARD FRAME AND COVER.”

4. Drawing C05 – Sewage Lift Station #2 Existing Conditions and Proposed Layout: Revise all references identifying the existing wet well as 1800 mm diameter to 1500 mm diameter. Delete all notes and indications requiring the existing SLS #2 wet well to be retained, reused, rehabilitated, or modified for reuse. The existing 1500 mm diameter wet well shall be demolished and removed. Provide a new 1800 mm ID precast concrete wet well complete with all associated excavation, bedding, backfill, connections and appurtenances required by the Contract Documents.

5. Drawing C06 – Sewage Lift Station #2 Wet-Well Plan & Section: Revise the drawing such that all work shown as modifications to or installation within the existing wet well shall instead apply to a new 1800 mm inside-diameter precast concrete wet well.

6. Drawing C06 – Sewage Lift Station #2 Wet-Well Plan & Section: Revise note for 1050 dia. manhole, “750 DIA. ADJUSTABLE FRAME AND COVER.” to read, “600 DIA. STANDARD FRAME AND COVER.”

7. Drawing C08 – Sewage Lift Station #3 Existing Conditions and Proposed Layout: Revise note, “EXISTING I.D. 2100 DIA. WET WELL TO BE DEMOLISHED...” to read, “EXISTING I.D. 1800 DIA. WET WELL TO BE DEMOLISHED...”

8. SLS #3 wet-well plan/section sheet: Revise all references identifying the existing wet well as 2100 mm diameter to 1800 mm diameter. The proposed wet-well dimensions are not changed by this correction.

TO THE SPECIFICATIONS

9. Section 01 00 00 General Requirements - Replace clause 1.1.3 with the following, “Remove the existing 1.5m diameter precast wet well including removal of all existing pumps, pump bases, pipes, fittings, etc., removal and installation of a new 1.8m diameter precast structure complete with hold-down ring.”

10. Section 33 32 13 – Packaged Wastewater Pumping Stations – Replace 3.2.2 with the following, “SLS #2 requires the existing wet well to be removed and replaced. Before the existing station is taken out of service, install, test and commission a temporary bypass pumping station with its own control panel and temporary power. Operate and maintain it 24/7 for the full duration of SLS #2 work until the new station has passed 3.7 testing and the 7-day operating period.”

A signed copy of each Addendum must also be included with the bid submission. Failure to include this Addendum may be cause for rejection. If you have any questions, please contact our office by email at procurement@afnwa.ca.

ALL OTHER SPECIFICATIONS, TERMS AND CONDITIONS REMAIN UNCHANGED.

Acknowledgement by Bidder:

Company Name: _____

Print Name: _____

Signed: _____

Date: _____

End of Addendum #3